

Bill of Quantity for Furnishing works for Baroda U.P. Bank	
Branch: Raunapar, Region - Azamgarh	
1. No off site prefabrication shall be allowed in any case. All fabrication shall be done at the site after getting the materials inspected by the architect	
5. Cable Managers to be provided in the tables and Counters wherever required.	
Branch at Raunapar	
2. No payment shall be made for any in completed or unsatisfactory work	
3. The Contractor should strictly follow the Booklet requirements of the Bank including the detailed drawings in the booklet. Any discrepancy between the booklet and the Specifications below should be brought to the notice of the Architect	
4. List of material to be strictly as per the booklet.	
6. All under frame should be properly treated with antitermite and waterproofing material	
7. All Locks in the drawers and doors etc. should be of Godrej	
8. All keyboard Trays and Drawers to be on Channel Sliding Mechanism.	
*The contractor to follow the banks colour Coding. Any other specified colour to be superceded by the Banks Colour code.	
*All board to be BWP. Of approved brand and if written BWR it should be superceded by BWP board/ply.	

Dated :- 02-12-2021

**Schedule of Quantity/ Tender of Furnishing work of Baroda U.P. Bank
Raunapar Branch Distt. & R.O. Azamgarh**

S.No.	Item's of work	Qty	Unit	Rate	Amount(Rs.)
1.	Bank Low ht. Counter 2'-6" wide made out of 19mm thick board with drawer unit and front side 12mm thick Etching Glass Supported with Teak wood or Aluminum member With 1.0 mm thick laminate on the top & Drawer unit shall be provided on one side while with space for CPU by its side pull out tray on slide shall be provided on each counter for keeping keyboard. all the exposed edges shall have 6 mm. TW lapping duly polished inside surface shall be enamel painted two coats over primer coats. It shall be locks & handles etc. provision for wire management shall be made. Complete work as per branch Manager/ Architect Satisfaction.	13.00	Rft		
2.	P/F of Bank Cash counter in partition two level cash counter 5'-0" long (with 3'-10" and 2'-6" height) counter for customer to be 1'-6" wide and counter to be 3'-0" wide with drawer unit made out of 19mm thick board with 1.0 mm thick laminate on top and front and other internal surface to be painted/polished complete as per item no.1	5.6	Rft		
3.	P/F of Cash cabin partition front-over the counter supported on 2'x1-1/2" sal				

wood frame work cover with 8.0 mm thk.
Etching glass supported of 1"x 1/2" beading
with book window in size 5"x6" center
of the counter with 2"x2" spacing Alu-
minium grill will be fixed in front of
partition Side partition supported 2"x1-1/2"
sal wood well seasoned structure with
a cost of antitermite treatment up to
3'-0" height framing of inside area with
2"x1-1/2" sal wood section 2'-0"c/c

(2)

- horizontal and vertical with both side
6mm thick ply&1.0mm thick laminates
both side. The upper portion up to 4'-0"
height shall be of 2-1/2"x2"x2-1/2"
Aluminum grill will be fixed complete
with all accessories and labour. 205.00 sft
4. P/F of Low Ht.(4'-6'' High) Partly glazed
Laminated Portion in **Branch Manager/
Advance dept. Cabin** the Under Framing
shall be of 2''x2'' sal wood (Anti termite Treatment)
for under framing at a max. distance 2'-0'' in each
direction. 6 mm th. Waterproof Ply shall be fixed on
two side & 1.0mm thick laminated shall be pasted over
its with chemical adhesive Provision shall be made
molding melamine Polished shall be fixed Wherever
necessary bottom 4'' width shall have 5mm th.
Plane glass 246.00 sft
5. P/F of Low Ht.(4'-6'' High) Laminated Portion
for UPS Space the Under Framing shall be of
2''x2''sal wood (Anti termite Treatment) for under
frame in at a max. distance 2'-0'' in each direction. °
6 mm th. Waterproof Ply shall be fixed on two side &
1.0mm thick laminated shall be pasted over its with
Chemical adhesive 50.00 sft
6. P/F Low height partition/**Wicket gate** all
specification as item No.4 . 14.00 sft
7. Providing and fixing in position double leaf
powder coated **Aluminum** entrance door

made of 14 guage thick sheet. All member shall be of 4"x1-3/4"section and bottom rail shall be of 5"x1-3/4"section with 6mm thick clear sheet glass including 4"dia 2 Nos. handles 10"long 2 Nos, Tower bolts, floor spring 2 Nos. lock etc. complete.

108.00 sft

8. P/F of **Godrej Night latch.**

1.0 No

9. P/F of **Godrej mortic lock**

2.0 Nos

10. P/F of **Door closer I.S.I mark**

1.0 Nos.

(3)

11. Providing and fixing **Writing desk** in position box type Wooden writing in public space of approximate size 4'-0" x 2'-0" made out of 19mm thick good approved quality ply with 6" to 9" wide wide pigeon hole type compartments in the front facade boxing for keeping pay-in-ship, book literature etc. These Writing table's must have laminates 1.0 mm thick on top writing desk and two sides of the Boxes. With beading, lipping, molding and painting /polishing complete.

1.0 No.

12. Suggestion box

1.0 No.

13. Check Drop Box

1.0 No.

14. Providing and fixing Aluminum grill in cash cabin Grill Size 2-1/2"x2"x2-1/2" will be fixed complete with all accessories & labour.

44.0 sft

15. Providing and fixing in position **Notice boards** of approximate size 3'-0"x2'-0" and 6" deep made out of 19mm thick ply with fully glazed shutter in front and soft board with felt cloth lining at the back inclusive of good approved quality lock to this shutter, hinges, fixtures, handle etc. and front laminate /painted complete as directed by bank architect.

1.0 No.

16. Providing and placing in position **side units** made out of 19mm board with 1.0mm laminate with sliding hinged shutters

(made out of 12mm thick ply with 1.0mm thick laminate on it) complete with handles etc. size 4'-0"x1'-6"x2'-6"

2.0 No.

17. Providing and fixing **Column/Wall paneling** (8'-6" Height) paneling all specification as per item no.4.

204.00 sft

(4)

18. Providing & fixing wooden **Filling Cabinet** 1'-6" deep to be fixed on the wall frame made out of 19mm thick commercial ply with siding hinge shutters made out of 12mm thick ply with 1.0mm laminate on the front & side other other internal surface to be painted as complete with handle, lock, wall catches etc.

65.00 sft

19. P/F in Position **Branch Manager Table** (Size-6'-0" x3'-0") made out of 19mm th. water proof board with 1.0 mm th. Laminated on all exposed surface (others external surface shall be painted with two coats of enamel paint over one coat of primer) It shall have one unit on one side while provision to be made for pull out tray on slides. the table to be finished in TW/ HW lapping & godrej lock, handles, footrest, latches all complete.

1.0 No.

20. P/F in Position **Officer Table** (Size-5'-0" x2'-6") made out of 19mm th. water proof board with 1.0 mm th. Laminated on all exposed surface (others external surface shall be painted with two coats of enamel paint over one coat of primer) It shall have one unit on one side while .

1.0 No.

21. **Distemper** on walls surface's with oil bound distemper two coats, with approved colour, Brand and manufacture of reqd. shade on under coateds wall surface to give an even shade over and including a priming coat with cement primer of approved brand and manufacture

such as Berger, Shalimar, Asian, Nerolac distemper
After the priming coat has been applied And
perfectly dried. All holes, scratches if Any shall
be required as mentioned in Preparations of
of surface and then first Coat of distemper
applied and allowed to Dry then second coat
distemper shall be Applied. Work completed
up to the bank satisfaction.

2450.00 sft

Total Rs.-----

(Rs. ----- Lacs ----- Thousand ----- Hundred ----- Only.)

For:- VISION ARCH

Rajesh kumar(Architect)

Resi.office: plot no. A-166

V.D.A. colony, Badalapur(chandmari), Varanasi

Mobile:9450165944/8957906861

Email: varch0036@gmail.com