



TENDER NOTICE

(For Empanelled Furnishers & Interior Decorators only)

FURNISHING, ELECTRICAL WORK & INTERIOR DECORATION OF TANDA CHAURAH A BRANCH : SANTKABIRNAGAR

IMPORTANT DATES

DATE OF ISSUE OF TENDER NOTICE	17.02.2024
LAST DATE AND TIME OF SUBMISSION OF TENDER	11.03.2024 up to 04:00 P.M.
DATE OF OPENING OF TENDER (FINANCIAL BID)	11.03.2024 at 04:30 P.M.

Baroda U.P. Bank

Premises & Equipment Department

Regional Office : Khalilabad

Near By-Pass Chauraha, Menhdawal Road, Khalilabad

District : SANTKABIR NAGAR

e-mail id: operations.roklbd@barodauprrb.co.in

Mobile: 9119603966

Regional Manager

Date: 17.02.2024

NOTICE INVITING TENDER

Sealed item rate short term tenders are invited on behalf of the Regional Manager, Baroda U.P.Bank, Regional Office Khalilabad from the Furnishers & Interior Decorators having valid Empanelment with the Baroda U.P. Bank for the work of FURNISHING, ELECTRICAL & INTERIOR DECORATION of TANDA CHAURAH Branch in Khalilabad Region.

- | | |
|--|---|
| 1. Issue of tender documents | : 17/02/2024 to 11/03/2024 upto 12.30 PM |
| 2. Last date of receipt of tender documents | : 11/03/2024 upto 4.00 PM |
| 3. Date of opening of tender documents | : 11/03/2024 at 4.30 PM |
| 4. Place of submission & opening of tender | : Baroda U.P. Bank, Regional Office Khalilabad |
| 5. Period for completion of work from order date | : Maximum 45 days |
| 6. Offer Validity | : 60 Days |
| 7. Retention percentage | : 10% (Ten percent) from final bill |
| 8. Defect liability period | : 12 months from the date of completion certificate issued by the Bank Architect. |
| 9. Release of retention money | : After 14 days from defect liability period. |

SUBMISSION OF TENDER

The tenders are to be submitted in a sealed envelope and clearly super scribed as

"Tender for FURNISHING ELECTRICAL WORK & INTERIOR DECORATION of TANDA CHAURAH Branch" and to be submitted at **Baroda U.P. Bank, Regional Office, Khalilabad.**

ENVELOPE TO BE CONTAINED

Envelope shall contain the priced Tender Volume

GENERAL INSTRUCTIONS TO TENDERERS

1. The term "Employers" or "Bank" shall mean "BarodaU.P.Bank", or its authorized representatives at Baroda U.P.Bank,Regional Office Khalilabad, Santkabir Nagar.
2. Theterm "Contractor" shall mean the successful tenderer to whom the Contract shall be awarded.
3. The"Works"shallmeanthe**"FURNISHING ELECTRICAL WORK & INTERIOR DECORATION of TANDA CHAURAH Branch at Baroda U.P. Bank, Regional Office Khalilabad, Santkabir Nagar (U.P.)"**
4. **The Contractor should quote the rates in figures and words .Any corrections or Over-writing should be initialed by the Contractor.**
5. TheContractor should submit the tenders with seal,signature and date on each Page.
6. The Contractor should submit the cost of the main items as per tender specifications. Further modification after awarding of the contract shall be not allowed unless there is specific instruction by the Bank/Architect to change specifications.
7. The contract is time-bound and the works are to be completed with in the time limits pecified in the notice inviting tenders.This is a working office and the contractor hastowork with no or minimum obstruction to its regular services.
8. The decision of Employer and the Architect is final and binding.

TERMS&CONDITIONS

1. Unless otherwise mentioned, all works are with no allowance for Lapse waste. Unless otherwise described or measured separately, price for all the items shall include all necessary straight &curved edges.
2. Any damage to the work before the site is handed over ,is to be replaced or made good a the expense of the contractor to the entire satisfaction of the Architect/Bank.
3. Income Tax, Other Tax as applicable shall be deducted at source as per the Income Tax Act/Rules.
4. The quantities indicated are subject to change. The payment of the bill shall be made as per the actual measurement as certified by the architect but not exceeding the total value quoted in the tender form.
5. The Architect or any officer of the Employers will be free to inspect the work at the site during the period of execution. Any suggestion of change or modification to improve the quality of work will be carried out subject to prior approval of the competent authority of the employers and that of the Architect.

6. In case of failure to take up the work even after accepting the work order ,or leaving the work incomplete,or for defective work not rectified, or violation of the terms and conditions, the contractor will be de-panelled/ blacklisted.
7. For any item of work not covered or any unforeseen items of work , payment will be made according to the rates approved for similar nature of work, the costing done by the Architect, as per current PWD schedule of rates ,or as per analysis of material cost, labour rate and profit to the Contractor at 10%.The Contractor must obtain prior approval in writing before undertaking such additional works.
8. The tenderer shall sign each & every page of the tender documents including the drawings attached hereto.
9. The amount is to be quoted in figures as well as in words. In case the rates quoted in words and in figures are invariance, the amount written in words shall be taken as final.
10. The Contractor shall make their own arrangement at their own cost for storing materials, plants, tools etc. The employers will not be liable for security of the Contractor's materials.
11. No tools or plants will be issued by the bank.
12. The Employer / Architect reserves the right to accept or reject any tender without assigning any reason whatsoever and the said decision shall be final and binding upon the tenderer.
13. In case of breach of contract by the Contractor for slow progress of work so any other claim of damage ,the Employer or the Architect may have the power to rescind the contract without furnishing further reasons thereof.
14. The Architect shall have the power to ask the contractor to furnish the sample/ color/test certificate from any Govt./ Authorized agent for any materials used/to be used in the Works, the expenditure of which is to be borne by the Contractor.
15. The Employer shall be not be liable for any damages or compensation payable as a consequence of any accident or injury to any workman or other persons in the employment of the Contractor or any sub-contractor.
16. On completion of the Works ,all rubbish, debris, materials ,tools, Laborers, etc. to be removed by the contractor from the site and the contractor will hand over the site clean& clear& in usable condition within 3days of completion of the works. Failing this, the employer may Dispose the materials at the cost of the contractor.
17. In case of any dispute ,the matter will be referred to the Regional Manager, Baroda U.P.Bank, Regional Office Khalilabad,Santkabir Nagar (UP).
18. Final Payment after completion of Project will be done with the certificate of Architect with deduction of retention money by the Bank.
19. The rates quoted in the tender shall exclude GST but include all excise tax, octroi & other taxes, no escalation of rates will be allowed under any circumstances.

Bill of Quantity for Furnishing works for Baroda U.P. Bank	
Branch at TANDA CHAURAH, Santkabr Nagar	
Region - Khalilabad	
1	No offsite prefabrication shall be allowed in any case. All fabrication shall be done at the site after getting the materials inspected by the architect
2	No payment shall be made for any in completed or unsatisfactory work
3	The Contractor should strictly follow the Booklet requirements of the Bank including the detailed drawings in the booklet. Any discrepancy between the booklet and the Specifications below should be brought to the notice of the Architect.
4	List of material to be strictly as per the booklet.
5	Cable Managers to be provided in the tables and Counters wherever required.
6	All under frame should be properly treated with ant termite and waterproofing material
7	All Locks in the drawers and doors etc. should be of Godrej
8	All keyboard Trays and Drawers to be on Channel Sliding Mechanism
*The contractor to follow the banks colour Coding. Any other specified colour to be superseded by the Banks Colour code	
*All board to be BWP. Of approved brand and if written BWR it should be superseded by BWP board/ply	

Summary**BARODA U. P. BANK****TANDA CHAURAH BRANCH DISTT. KHALILABAD**

sno	Description	Section	Amount of Tender
1.	Furnishing works	in digits	
		in words	
2.	Electrical	in Digits	
		In words	
	TOTAL	in Digits	
		In words	
	GST 18%	In words	
	GRAND TOTAL	in Digits	

Note :-

1. All materials to be used strictly follow the list of approved materials.
2. Any deviation in the use of materials at site other than approved materials list will not be permitted and the bank may cancel the contract at any time for any such misconduct & colour as per bran manual.
3. The workman ship and quality of work should be of good quality and to be satisfaction level of the bank's architect and bank

TENDER OF FURNISHING WORKS FOR **BARODA U. P. BANK** SITUATED AT TANDA CHAURAH
BRANCH , DISTT. KHALILABAD.

1. FURNISHING WORKS:-

SNO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	FALSE CEILING:- (Gyp board) / :-				
	Providing and fixing Gypsum false ceiling as per India Gypsum specification for ceiling with drops as per drawing including of providing and fixing G.I. Frame work as per specification of India gypsum at a distance of 2'0"c/c both ways complete with 12.5 mm board and all necessary perimeter channels etc. No extra payment will be made for the cutting of light points, stained glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work.	0.0	SQ.FT.		
1.A	24" x 24" Grid False Ceiling (FINE FISSURED PLANKS): Providing and Fixing False ceiling Grid using hot dipped Galvanized steel sections, exposed surface chemically cleaned capping pre-finished inbaked polyester paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x24mm at 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x600mm. The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fibre wool board having Fire rating of 60 min. as per BS 476/23 of 1987, Noise reduction co-eff. (NRC) of 0.50, Light	0.0	SQ.FT.		
2.	PARTITION				
	Providing and fixing partition in position as per design with 2" x 1.5" Aluminum section finished frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and to be treated with anti termite oil. The measurement will be taken upto the false ceiling visible height in case of full height partition. The frame work will be cladded with 10mm thk comm. Ply both sides and to be finished with approved 1 mm laminate (color with				

	vertical grain) as per design with adhesive. 3" high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing class. In the glazed partition 8 to 10mm thk. Glass with etching and bank logo.				
A	PARTLY GLAZED PARTITION				
I	PARTLY GLAZED CASH CABIN PARTITION UPTO 7'-0" HT.	80.00	SQ.FT.		
II	PARTLY GLAZED MANAGER CABIN PARTITION UPTO 5'-0" HT.	110.00	SQ.FT.		
III	PARTLY GLAZED LOW HEIGHT PARTITION UPTO 4'-0' HT.	100.00	SQ.FT.		
IV	Front Glass in Low Height Counters	25.00	SQ.FT.		
B	BLOCKED PARTITION				
I	BLOCKED PARTITION UPTO 10'-0" HEIGHT RECORD ROOM PARTITION:-	270.00	SQ.FT.		
3	DOORS				
	Providing and fixing solid core 38mm solid core flush door finished with lippings in all side with necessary door hinges, cylindrical looks (golden, Godrej), door clouser, door stoppers, etc with a frame work of T.W./ Beech wood size 75mm x 62.5mm with necessary hold fast fixed to the wall/partition. 1 mm laminate to be fixed on both sides duly finished, edges to be finished with wooden lippings. A wooden molding size 1.5" x 2/8" to be provided all along the periferi of the frame work in the both sides. All the wooden area to be duly polished as per specification of the Architect. In case of Partly glazed door 8mm thk etched or plain glass with granular blasting/sand blasting as per design of the Architect to be fixed with necessary moldings.				
I	Flap Door	14.00	Sq.fts.		
2.	FULLY GLAZED ENT. DOOR WITH POWER COATED ALUMINIUM PARTITION WITH HANDLE AND LOCK:-	70.00	SQ.FT.		
4.	CASH COUNTER:-				
	For customer as per layout with provision of 3'-9" high, 2'-6" deep with shelf for CPU and storage unit out of 18 mm thick commercial board with 1.00 mm thick laminate on all exposed surfaces with key board tray with telescopic slides. All edgings. Margin etc. out of polished steamed.	5'-0"	RFT.		
5.	OFFICER COUNTER				
	For customer as per layout with provision of 2'-6" high, 2'-6" deep with shelf for CPU	13'-6"	Rft.		

	and storage unit out of 18 mm thick commercial board with 1.00 mm thick laminate on all exposed surfaces. With key board tray with telescopic slides. All edgings. Margin etc. out of polished steamed.				
	<p>Manager Table:- 6' x 3' H = 2'-6"</p> <p>Providing and fixing MANEGER'S TABLE 6'-0"x3'-0"x2'-6" (ht.) and 10mm beveled glass of approved make to be fitted on to p obtain the total height of 2'-6" as per detailed drawing . made up of 19 mm commercial board of approved make the finished with 1 mm thick laminate of approved make and shad as approved as par detailed drawing. Table shall be provided with 3 drawers sliding on telescopic channels with proper locking arrangements and keyboard with telescope channels tabletop shall be finished with 1.0 mm thick laminate of approved shade & quality . The work includes provided and fixing locks , wire manager , spirit polishing of steam beach bending etc. complete in all respects to the entire satisfaction of the architect.</p>	1 no.	each		
	<p>Officer Table:- 4' -6"x 2'-6" H = 2'-6"</p>	0.0	each		
6.	STORAGE				
	Providing and fixing Full height storage 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (color, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block board and should play on drawer slidign castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / moldings duly polished all complete.				
	Low Height storage (2'-6" ht).	50.00	SQ.FT.		
	Full height storage (7'-0" ht).	90.00	SQ.FT.		
7.	CHEQUE DROP BOX Providing and making Suggestion box 1.5'x1'x 9" deep)as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white paited glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hardwares and locking and side opening arrangements	1 NO.	EACH		
8.	SUGGESTION BOX Providing and making Suggestion box 1.5'x1'x9" deep)as per design & pattern	1 NO.	EACH		

	with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hardwares and locking and side opening arrangements				
9.	WALL MOUNTED WRITING TABLE 1'-3" TO 1'-6" WIDE AND LENGTH 5'-0"				
10.	NOTICE BOARD (1200x900) Providing & fixing Notice Board the tag board of approved make & design, of size 4' X 3', with anodized aluminum boarder/frame type. The board should be 3/4" th. Strow board with belvet type fabric lining of apprd. Colour.	2 NOS.	EACH		
11	METER BOX Providing and fixing Meter Box 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (color, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block board and should play on drawer slidign castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / moldings duly polished all complete.	36.00	SQ.FT.		
	Total			RS.	

2. ELECTRICAL WORKS:-

SNO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Wiring for light points, fan points, bell points, sockets etc. with 1.5 Sq.mm PVC insulated, 1100 V grade grade copper conductor wires and 1.0 Sq mm copper earth wire and 1.0 Sq mm copper earth wire in concealed/surface using PVC (Heavy)25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where where ever required) and chromium plated brass screws/rowel plugs etc.. The conduits to be laid in ceiling with proper clamps/wall/floor and filling the chase with cement mortar and finish the same in original form/wooden partition/above false ceiling with proper clamps (wherever required as per standard specification.				
	NOTE:				
	i) Each circuit shall have independent earth wire.				
	ii) Each point shall be earthed.				
	a) One light point controlled by one 6A modular one way switch.	35 nos	each		
	b) A set of two light points controlled by one 6A modular one way switch.	5 nos.	each		
	c) One Ceiling fan point with 6A 3 pin socket controlled by one 6A modular one way switch. The switch should be at switch board level.	08 Nos.	each		
	d) One exhaust fan point with ceiling rose controlled by one 6A modular one way switch.	1 nos	each		
	e) One call bell point with ceiling rose/6A 3Pin socket controlled by one 6A modular bell push switch.	1 nos.	each		
	[FOR ITEM NO. "a" TO "e" ALL MOUNTING BOXES, INNER PLATES, MODULES, COVER PLATES ETC. SHALL BE CRABTREE MEGA SERIES, PLATINUM RANGE MATERIAL (OR EQUIVALENT OF ABB/M.K.) ONLY]				
2.	CIRCUIT WIRING :circuit wiring starting from DB to point control box/switch box using PVC (Heavy) 25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where ever required) with 2x2.5 sqmm PVC insulated 1100V grade multi-stranded copper conductor wire and 1.5 sqmm PVC insulated earth wire and 1.5sqmm. PVC insulated earth Wire (color code to be used).Identification ferrules at both end to beprovided. (Flexible conduit/elbow NOT allowed)	300.00	RMT.		
3.	POWER POINTS				
	Same as serial no. 1, but wiring for 16A 6-Pin socket by using 4 sq mm PVC insulated 1100V grade copper conductor wire with independent 2.5 sqmm earth wire from D.B. to first 1st. Socket and 1st socket to 2nd Socket with 2.5 sqmm and 1.5 sqmm earth				

	wire including providing and fixing of 16A 6-Pin socket with 16A switch				
	1. a) Power point with 4sqmm copper	05.00	EACH		
	FOR ITEM NO. "a" & "b" SHALL BE CRABTREE (OR EQUIVALENT OF ABB/M.K.) MAKE MODULAR/DOUBLE MODULE WITH ALL ACCESSORIES ONLY]]				
4.	DISTRIBUTION BOARDS:				
	Supplying, installation, testing and commissioning of DOUBLE DOOR type distribution boards ORIGINAL FACTORY FABRICATED ONLY) of following specifications:				
	B) 4-WAY TPN DB (LIGHT & FAN DB)				
	INCOMER :40A 4P. MCB-1No.	1 NO.	EACH		
	OUTGOING: 10A SP MCB-12Nos.				
	C) Supplying & Fixing of 1 no. 40A DP MCB in 4 way SPN DB (FOR UPS OUT-PUT AT S/R)	1 NO.	EACH		
5	MAIN PANEL				
	A.) Designing, manufacturing, installation, testing and commissioning of cubical type MAIL PANEL made from 16 SWG CRCA sheet steel, "[type base M.S. Channel for grouting on floor complete with MCCBs, MCBs, Meters, C.T. etc. complete in all respect, insulated bus-bar with heat shrinkable PVC sleeve in suitable bus-bar chamber, wiring, name plates, danger plate, earth-bus etc.& comprising of compartments with hinged doors and rubber gasket, bus-bar chamber with bolted door and rubber gasket etc. The panel being of dust & vermin proof construction and to be painted with primer and smoke gray paint (minimum two coats) to look attractive. The panel should be comprising with the followings: Degree of Protection IP-54)	1 NO.	EACH		
	INCOMER:				
	100A HRC fuse base and bridge with HRC fuses Natural link for three phase four wire system- 1Set				
	100A, 25KA, 4P MCCB -----1 NO.				
	100A 4-P, ON LOAD change over switch-1no.				
	160A capacity aluminum bus-bar with heat shrinkable proper insulation with color coaded.				
	Digital ammeter and voltmeter with selector switches.				
	R-Y-B phase indicators with 2A backup HRC fuse.				
	OUTGOING:				
	63A 4-P MCCB, 25KA,-----3Nos.				
	63A 4-P ON LOAD change over switch (FOR SYSTEM ROOM/ATM)-----1No.				
	40A 4-P MCCB, 25KA-----1 No.				

	32A TPN MCB, 25KA-----1No.				
6	Supplying, installation, testing and commissioning of following light fixtures, fans etc.				
	a) PHILIPS/WIPRO/C.G./HAVELLS Make light fixtures				
	i) S/F of LED 4' wide (patti) Light fixtures	26	NOS.		
	ii) S/F of LED 2' wide (patti) Light fixtures	01	NOS.		
	b) CROMPTON GREAVES make fans				
	1. Ceiling fan	08	Nos.		
	2. 12" Exhaust fans with clamps, bolt/dash fastener by grouting on wall for Toilets.	1	NOS		
7.	COMPUTER POINT				
	a. Wiring with sx2.5 sqmm + 1x1/5 sq mm PVC insulated 1100 V grade multistranded copper conductor wires in 2 mm thick PVC conduit from UPSDB to computer point. Each point to have 3 nos 6A -5 Pin modular type sockets, one 6A indicator at below the top of table/counter and controlled by one 16A modular switch at above the table top in wooden partition with all accessories, inner/outer plates, metal box etc. and to be fixed on wooden partitions/by grouting on wall etc. as per the requirement at site.	06	nos		
	b. Cut out 63 AP	04 nos.	Nos		
	c. UPS wiring for UPS	80.00	Mtrs.		
8.	TELEPHONE POINT / DATA CABEL				
a.	Providing/Laying of Cat 6 Cable	200.00	Mt.		
b.	Patch Cord 2 Meter	06	Nos.		
c.	Patch Cord 1Meter	06	Nos.		
d.	I/O box	06	Nos.		
e.	Tray, cable manager and 9 U Rack <u>Note:-</u> All products should be D-Link, Tp Link or equivalent International Quality.	1 no.	No.		
9.	a) Providing and fixing of following earth station as per IS:3043, with water pouring pipes, GI funnels, masonry brick chamber with CI cover, including excavation & refilling of pit after filling with charcoal, salt and sand, identification				

	of pit as required.				
	i) 600x600x3.15mm Copper Plate Earth Station.	2	No.		
	b) Supplying, Laying and terminating of the following tapes/ wires with suitable G.I./copper clamps.				
	i) 25x3mm Copper strip with copper clamps.	50.00	Rmt.		
	Total			Rs.	